

PROJECT(S): MILTON - GEORGIA STP 2510(1)S

CONTRACT ID : 05C158
 CALL ORDER : 002
 CONTRACT TIME : 99 CD

CONTRACT DESCRIPTION :
 MILTON-GEORGIA STP 2510(1)S: BEGINNING AT STATION 4+96 (MM 0.094) OF US ROUTE 7 IN THE TOWN OF MILTON AND EXTENDING NORTHERLY ALONG US ROUTE 7 THROUGH THE TOWN OF MILTON AND INTO THE TOWN OF GEORGIA FOR A DISTANCE OF APPROXIMATELY 45,593 FEET (8.635 MILES) TO THE END OF THE PROJECT AT STATION 47+47 (MM 0.899) IN THE TOWN OF GEORGIA.

TOWN(S) : MILTON GEORGIA
 COUNTY : STATEWIDE/MUTIPLE COUNTIES
 DISTRICT : D000

WORK TO BE PERFORMED UNDER THIS PROJECT INCLUDES RESURFACING OF THE EXISTING HIGHWAY WITH COLD PLANING AND OVERLAY SECTIONS (LEVELING AND WEARING COURSE), NEW PAVEMENT MARKINGS, GUARDRAIL INSTALLATION, DRAINAGE IMPROVEMENTS AND INCIDENTAL ITEMS.

RANK	VENDOR NO./NAME	TOTAL BID	% OVER LOW BID
1	115009280610 PIKE INDUSTRIES, INCORPORATED	\$ 1,939,447.50	100.0000%
2	12000589 FRANK W. WHITCOMB CONSTRUCTION CORPORATION	\$ 2,164,673.00	111.6129%

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) 115009280610 PIKE INDUSTRIES, INC.		(2) 12000589 F. W. WHITCOMB CONSTRUCTION		()	
		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
SECTION 0001 ROADWAY							
0005 203.15 COMMON EXCAVATION	160.000 CY	15.00000	2400.00	25.00000	4000.00		
0010 203.16 SOLID ROCK EXCAVATION	50.000 CY	120.00000	6000.00	200.00000	10000.00		
0015 203.28 EXCAVATION OF SURFACES AND PAVEMENTS	30.000 CY	25.00000	750.00	50.00000	1500.00		
0020 203.30 EARTH BORROW	800.000 CY	3.00000	2400.00	5.00000	4000.00		
0025 204.22 TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	1.000 CY	75.00000	75.00	75.00000	75.00		
0030 210.10 COLD PLANING, BITUMINOUS PAVEMENT	36500.000 SY	1.00000	36500.00	2.75000	100375.00		
0035 301.28 SUBBASE OF CRUSHED GRAVEL, FINE GRADED	725.000 TON	12.00000	8700.00	20.00000	14500.00		
0040 402.13 AGGREGATE SHOULDERS, RAP	2350.000 TON	5.00000	11750.00	19.50000	45825.00		

VERMONT AGENCY OF TRANSPORTATION
 LETTING DATE : 06/08/07 11:00 A.M.
 RESULTS OF BIDS

RUN DATE : 06/08/07
 CALL : 002 PAGE : 2

PROJECT(S): MILTON - GEORGIA STP 2510(1)S

CONTRACT ID : 05C158

		(1) 115009280610 PIKE INDUSTRIES, INC.		(2) 12000589 F. W. WHITCOMB CONSTRUCTION		()		
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0045 404.65	EMULSIFIED ASPHALT	410.000 CWT	60.00000	24600.00	55.00000	22550.00		
0050 406.50	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	1.000 LU	1.00000	1.00	1.00000	1.00		
0055 490.30	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 58-34)	15600.000 TON	57.00000	889200.00	62.75000	978900.00		
0060 490.31	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	1.000 LU	1.00000	1.00	1.00000	1.00		
0065 490.32	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	1.000 LU	1.00000	1.00	1.00000	1.00		
0070 490.34	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	1.000 LU	1.00000	1.00	1.00000	1.00		
0075 516.10	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	66.000 LF	100.00000	6600.00	95.00000	6270.00		
0080 601.0010	15" CSP .064 (2-2/3 X 1/2)	10.000 LF	100.00000	1000.00	175.00000	1750.00		
0085 601.995	CLEANING CULV. PIPE, IN-PLACE [0 TO 24 IN., INCL.]	300.000 LF	20.00000	6000.00	25.00000	7500.00		
0090 601.996	CLEANING CULV. PIPE, IN-PLACE [GREATER THAN 24 IN.]	300.000 LF	20.00000	6000.00	25.00000	7500.00		
0095 604.40	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	17.000 EACH	500.00000	8500.00	800.00000	13600.00		
0100 604.412	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	5.000 EACH	1500.00000	7500.00	1500.00000	7500.00		
0105 604.42	CHANGING ELEVATION OF SEWER MANHOLES	20.000 EACH	500.00000	10000.00	800.00000	16000.00		
0110 608.15	POWER GRADER RENTAL	90.000 HR	25.00000	2250.00	35.00000	3150.00		
0115 608.25	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	240.000 HR	60.00000	14400.00	75.00000	18000.00		
0120 608.30	POWER BROOM RENTAL, TYPE I	90.000 HR	15.00000	1350.00	20.00000	1800.00		
0125 608.31	POWER BROOM RENTAL, TYPE II	50.000 HR	50.00000	2500.00	50.00000	2500.00		

VERMONT AGENCY OF TRANSPORTATION
 LETTING DATE : 06/08/07 11:00 A.M.
 RESULTS OF BIDS

RUN DATE : 06/08/07
 CALL : 002 PAGE : 3

PROJECT(S): MILTON - GEORGIA STP 2510(1)S

CONTRACT ID : 05C158

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY		(1) 115009280610 PIKE INDUSTRIES, INC.		(2) 12000589 F. W. WHITCOMB CONSTRUCTION		()	
			UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0130 608.37 TRUCK RENTAL	480.000	HR	40.00000	19200.00	55.00000	26400.00		
0135 608.40 LOADER RENTAL, TYPE I	130.000	HR	30.00000	3900.00	25.00000	3250.00		
0140 613.10 STONE FILL, TYPE I	900.000	CY	40.00000	36000.00	75.00000	67500.00		
0145 616.27 CAST-IN-PLACE CONCRETE CURB, TYPE A	20.000	LF	150.00000	3000.00	150.00000	3000.00		
0150 616.47 BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	240.000	TON	150.00000	36000.00	125.00000	30000.00		
0155 617.10 RELOCATE MAILBOX, SINGLE SUPPORT	5.000	EACH	150.00000	750.00	150.00000	750.00		
0160 617.12 RELOCATE MAILBOX, MULTIPLE SUPPORT	3.000	EACH	170.00000	510.00	180.00000	540.00		
0165 618.10 PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	195.000	SY	75.00000	14625.00	100.00000	19500.00		
0170 618.15 BITUMINOUS CONCRETE SIDEWALK	4.000	TON	400.00000	1600.00	300.00000	1200.00		
0175 618.30 DETECTABLE WARNING SURFACE	270.000	SF	50.00000	13500.00	55.00000	14850.00		
0180 619.17 YIELDING MARKER POSTS	10.000	EACH	50.00000	500.00	35.00000	350.00		
0185 621.20 STEEL BEAM GUARDRAIL, GALVANIZED	1875.000	LF	18.00000	33750.00	14.50000	27187.50		
0190 621.205 STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	6900.000	LF	20.00000	138000.00	16.50000	113850.00		
0195 621.50 MANUFACTURED TERMINAL SECTION, FLARED	24.000	EACH	1950.00000	46800.00	1700.00000	40800.00		
0200 621.60 ANCHOR FOR STEEL BEAM RAIL	8.000	EACH	750.00000	6000.00	550.00000	4400.00		
0205 621.80 REMOVAL AND DISPOSAL OF GUARDRAIL	9600.000	LF	1.00000	9600.00	1.00000	9600.00		
0210 629.20 ADJUST ELEVATION OF VALVE BOX	33.000	EACH	100.00000	3300.00	250.00000	8250.00		
0215 630.10 UNIFORMED TRAFFIC OFFICERS	1000.000	HR	30.00000	30000.00	55.00000	55000.00		
0220 630.15 FLAGGERS	5000.000	HR	15.00000	75000.00	22.00000	110000.00		

VERMONT AGENCY OF TRANSPORTATION
 LETTING DATE : 06/08/07 11:00 A.M.
 RESULTS OF BIDS

RUN DATE : 06/08/07
 CALL : 002 PAGE : 4

PROJECT(S): MILTON - GEORGIA STP 2510(1)S

CONTRACT ID : 05C158

		(1) 115009280610		(2) 12000589		()		
		PIKE INDUSTRIES, INC.		F. W. WHITCOMB CONSTRUCTION				
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0225 631.10		LUMP	20000.00000	20000.00	12000.00000	12000.00		
	FIELD OFFICE, ENGINEERS							
0230 631.17		LUMP	100.00000	100.00	500.00000	500.00		
	TESTING EQUIPMENT, BITUMINOUS							
0235 631.25		1.000 LU	3000.00000	3000.00	3000.00000	3000.00		
	FIELD OFFICE TELEPHONE (N.A.B.I.)							
0240 634.10		520.000 HR	1.00000	520.00	1.00000	520.00		
	EMPLOYEE TRAINEESHIP							
0245 635.11		LUMP	85000.00000	85000.00	100000.00000	100000.00		
	MOBILIZATION/DEMOBILIZATION							
0250 641.10		LUMP	70000.00000	70000.00	75000.00000	75000.00		
	TRAFFIC CONTROL							
0255 641.12		LUMP	5000.00000	5000.00	6656.00000	6656.00		
	PUBLIC RELATIONS OFFICER							
0260 641.15		2.000 EACH	4000.00000	8000.00	2500.00000	5000.00		
	PORTABLE CHANGEABLE MESSAGE SIGN							
0265 646.402		92500.000 LF	0.50000	46250.00	0.27000	24975.00		
	DURABLE 4 INCH WHITE LINE, THERMOPLASTI							
0270 646.412		90100.000 LF	0.50000	45050.00	0.27000	24327.00		
	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC							
0275 646.452		560.000 LF	1.00000	560.00	0.60000	336.00		
	DURABLE 8 INCH YELLOW LINE, THERMOPLASTIC							
0280 646.482		760.000 LF	5.00000	3800.00	4.00000	3040.00		
	DURABLE 24 INCH STOP BAR, THERMOPLASTIC							
0285 646.492		279.000 EACH	75.00000	20925.00	40.00000	11160.00		
	DURABLE LETTER OR SYMBOL, THERMOPLASTIC							
0290 646.501		415.000 LF	15.00000	6225.00	12.00000	4980.00		
	DURABLE CROSSWALK MARKING, TYPE I TAPE							
0295 646.602		92500.000 LF	0.05000	4625.00	0.03000	2775.00		
	TEMPORARY 4 INCH WHITE LINE, PAINT							
0300 646.612		90100.000 LF	0.05000	4505.00	0.03000	2703.00		
	TEMPORARY 4 INCH YELLOW LINE, PAINT							
0305 646.682		760.000 LF	1.00000	760.00	1.00000	760.00		
	TEMPORARY 24 INCH STOP BAR, PAINT							
0310 646.692		227.000 EACH	5.00000	1135.00	5.00000	1135.00		
	TEMPORARY LETTER OR SYMBOL, PAINT							
0315 646.702		490.000 LF	4.00000	1960.00	4.00000	1960.00		
	TEMPORARY CROSSWALK MARKING, PAINT							
0320 646.76		1500.000 EACH	0.75000	1125.00	1.00000	1500.00		
	LINE STRIPING TARGETS							

VERMONT AGENCY OF TRANSPORTATION
 LETTING DATE : 06/08/07 11:00 A.M.
 RESULTS OF BIDS

RUN DATE : 06/08/07
 CALL : 002 PAGE : 5

PROJECT(S): MILTON - GEORGIA STP 2510(1)S

CONTRACT ID : 05C158

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY		(1) 115009280610 PIKE INDUSTRIES, INC.		(2) 12000589 F. W. WHITCOMB CONSTRUCTION		()	
			UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0325 649.31 GEOTEXTILE UNDER STONE FILL	4050.000	SY	3.50000	14175.00	2.00000	8100.00		
0330 651.15 SEED	120.000	LB	10.00000	1200.00	15.00000	1800.00		
0335 651.18 FERTILIZER	1000.000	LB	10.00000	10000.00	3.00000	3000.00		
0340 651.20 AGRICULTURAL LIMESTONE	4.000	TON	1000.00000	4000.00	800.00000	3200.00		
0345 651.25 HAY MULCH	4.000	TON	1000.00000	4000.00	800.00000	3200.00		
0350 651.35 TOPSOIL	200.000	CY	20.00000	4000.00	30.00000	6000.00		
0355 653.20 TEMPORARY EROSION MATTING	900.000	SY	3.75000	3375.00	5.00000	4500.00		
0360 675.20 TRAFFIC SIGNS, TYPE A	575.000	SF	13.50000	7762.50	13.50000	7762.50		
0365 675.50 REMOVING SIGNS	131.000	EACH	20.00000	2620.00	10.00000	1310.00		
0370 675.60 ERECTING SALVAGED SIGNS	44.000	EACH	40.00000	1760.00	25.00000	1100.00		
0375 676.10 DELINEATOR WITH STEEL POST	42.000	EACH	50.00000	2100.00	38.00000	1596.00		
0380 678.22 VEHICLE LOOP DETECTOR	500.000	LF	12.00000	6000.00	15.00000	7500.00		
0385 690.50 PRICE ADJUSTMENT, FUEL (N.A.B.I.)	1.000	LU	1.00000	1.00	1.00000	1.00		
0390 900.640 SPECIAL PROVISION (DURABLE CROSSWALK MARKING,	75.000	LF	200.00000	15000.00	250.00000	18750.00		
0395 675.301 AA1 FLANGED CHANNEL SIGN POST	1440.000	LF	10.00000	14400.00	7.50000	10800.00		
0400 675.341 AA2 SQUARE TUBE SIGN POST AND ANCHOR SECTION TOTALS	1440.000	LF						
			\$	1,939,447.50	\$	2,164,673.00	\$	
COMMON ITEMS TOTAL			\$	1,939,447.50	\$	2,164,673.00	\$	
CONTRACT TOTALS (LOW COST)			\$	1,939,447.50	\$	2,164,673.00	\$	