

AGGREGATE SURFACE COURSE, SIDEWALK/TRAIL

****From Statewide STP NWRT(1)**

- xx. DESCRIPTION. This work shall consist of furnishing and placing a wearing course of approved aggregate on a prepared surface.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 401 of the Standard Specifications.

- xx. MATERIALS. Aggregate for Aggregate Surface Course, Sidewalk/Trail shall meet the gradation requirements of the following table as determined in accordance with AASHTO T 27 and AASHTO T 11:

TABLE A - AGGREGATE SURFACE COURSE, SIDEWALK/TRAIL

Sieve Designation	Percentage by Mass (Weight) Passing Square Mesh Sieves
12.5 mm (1/2 inch)	100
9.5 mm (3/8 inch)	80 to 100
4.75 mm (No. 4)	60 to 90
1.18 mm (No. 16)	20 to 40
600 µm (No. 30)	14 to 30
300 µm (No. 50)	10 to 25
150 µm (No. 100)	8 to 15
75 µm (No. 200)	0 to 10

- xx. PLACING. The maximum layer thickness for placement of Aggregate Surface Course, Sidewalk/Trail shall be 75 ± 10 mm (3 ± 1/2 inches) after compaction.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Aggregate Surface Course, Sidewalk/Trail) to be measured for payment will be the number of cubic meters (cubic yards) used in the complete and accepted work, as determined by the Plan dimensions of the compacted material or as ordered by the Engineer. No allowance will be made for material placed to a depth greater than that shown on the Plans unless ordered by the Engineer.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Aggregate Surface Course, Sidewalk/Trail) will be paid for at the Contract unit price per cubic meter (cubic yard). Payment will be full compensation for performing the work specified and for furnishing all materials, labor, tools, equipment, and incidentals necessary to complete the work.

Water used for obtaining the required compaction will not be paid for separately but will be considered incidental to Special Provision (Aggregate Surface Course, Sidewalk/Trail).

Payment will be made under:

Pay Item

Pay Unit

10/5/2011

900.608 Special Provision (Aggregate Surface
Course, Sidewalk/Trail)(FPQ)

Cubic Yard