

BOX BEAM GUARDRAIL, PAINTED

****From Newport City BRO 1449(25)**

- xx. DESCRIPTION. This work shall consist of furnishing and erecting painted box beam guardrail as shown in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Sections 513 and 621 of the Standard Specifications.

- xx. FABRICATION. Guardrail shall be painted black following fabrication. The coating system shall meet the requirements of Subsection 708.03.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Box Beam Guardrail, Painted) to be measured for payment will be the number of meters (linear feet) installed in the complete and accepted work, measured from center to center of end posts. An additional 300 mm (1 foot) of guardrail will be allowed for each overhang.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Box Beam Guardrail, Painted) will be paid for at the Contract unit price per meter (linear foot). Payment will be full compensation for furnishing, transporting, handling, and placing the material specified, and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.640 Special Provision (Box Beam Guardrail, Painted)	Meter (Linear Foot)