

BRIDGE RAILING, GALVANIZED HDSB/FASCIA MOUNTED/HAND RAIL

****From Readsboro BRO 1441(25)**

- xx. DESCRIPTION. This work shall consist of furnishing and erecting galvanized heavy duty fascia mounted bridge railing with hand rail in accordance with the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 525 of the Standard Specifications.

- xx. FABRICATION AND INSTALLATION. Rail posts shall be fabricated to a length of 4'-3" (1320 mm) and installed as detailed in the Plans.

The Contractor shall refer to Agency Standard Drawing SB-R6-82M for additional information and requirements.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Bridge Railing, Galvanized HDSB/Fascia Mounted/Hand Rail) to be measured for payment will be the number of meters (linear feet) of rail used in the complete and accepted work. Measurement will be made along the face of rail from end to end or between the pay limits specified.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Bridge Railing, Galvanized HDSB/Fascia Mounted/Hand Rail) will be paid for at the Contract unit price per meter (linear foot). Payment will be full compensation for detailing, furnishing, handling, placing, delineating, galvanizing, applying grease rustproof compound, and painting the railing components; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.640 Special Provision (Bridge Railing, Galvanized HDSB/Fascia Mounted/Hand Rail) (Painted Black)	Meter (Linear Foot)