

BRIDGE RAILING, TRUSS

****From Hartford (Wilder) STP 1444(35)**

- xx. DESCRIPTION. This work shall consist of furnishing and attaching bridge railing to an existing steel pony truss bridge as shown on the Plans and as directed by the Engineer.

The work under this section shall be performed in accordance with these provisions, the Plans, and Section 525 of the Standard Specifications.

- xx. MATERIALS. Materials for Bridge Railing, Truss shall meet the requirements of Subsection 732.03 and as specified in the Plans.

- xx. CONSTRUCTION REQUIREMENTS. Bridge Railing, Truss shall be installed as detailed on the Plans and as directed by the Engineer.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Bridge Railing, Truss) to be measured for payment will be the number of meters (linear feet) of railing placed in the complete and accepted work, measured within the pay limits designated in the Plans.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Bridge Railing, Truss) will be paid for at the Contract unit price per meter (linear foot). Payment will be full compensation for detailing, furnishing, handling, and placing the materials specified; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.640 Special Provision (Bridge Railing, Truss)	Meter (Linear Foot)