

CHAIN-LINK FENCE, CONCRETE MOUNTED

****From Bennington AC NH 019-1(52)**

- xx. DESCRIPTION. This work shall consist of furnishing and erecting 1.8 m (6 feet) chain-link fence and posts on top of a precast concrete box structure as shown in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 620 of the Standard Specifications.

- xx. CONSTRUCTION REQUIREMENTS. Fence posts shall be set in galvanized steel mounting flanges as shown in the Plans and as directed by the Engineer.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Chain-Link Fence, Concrete Mounted) to be measured for payment will be number of meters (linear feet) of fence installed in the complete and accepted work. Measurement will be along the top of the fence from inside to outside of the corner posts.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Chain-Link Fence, Concrete Mounted) will be paid for at the Contract unit price per meter (linear foot). Payment will be full compensation for furnishing, transporting, handling, assembling, and placing the materials specified, including all posts and hardware, and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.640 Special Provision (Chain-Link Fence, Concrete Mounted)	Meter (Linear Foot)