

COMMERCIAL SIGNS

**\*\*From Brandon NH 019-3(495)**

- xx. DESCRIPTION. This work shall consist of removing, and removing and resetting, commercial sign(s) at the locations indicated in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 675 of the Standard Specifications.

- xx. MATERIALS. Concrete for sign foundations shall conform to the requirements of Section 541 for Concrete, Class B.

- xx. REMOVING SIGNS. For signs not re-used on the project, the Contractor shall coordinate the return of signs to the property owner and shall deliver all components of the removed sign including posts, sign panels, and hardware to the location indicated by the Owner.

- xx. RESETTING SIGNS. The Contractor shall re-use all existing materials to the greatest extent possible for the resetting of commercial signs and commercial signs with planters. During removal activities of commercial signs to be reset, if sign posts are found to be rotted or damaged to the extent that they cannot be re-used to support the signs in their new locations, the Contractor shall supply new posts of equal size and material. If planter materials are found to be rotted or damaged to the extent that they cannot be re-used to re-install the planters in their new locations, the Contractor shall supply new materials of similar size and type needed to reconstruct the planters to the satisfaction of the Engineer.

The Contractor shall construct foundations for commercial signs to be reset matching the size and depth of the foundation of the sign at its existing location, or shall construct foundations to a size and depth necessary to support the sign as directed by the Engineer. The Contractor shall supply new hardware and accessories as needed for resetting of existing commercial signs and re-installation of wood planters.

- xx. METHOD OF MEASUREMENT. The quantities of Special Provision (Remove and Reset Commercial Sign) and Special Provision (Remove and Reset Commercial Sign with Wood Planter) to be measured for payment will be the number of signs removed and reset in the complete and accepted work.

The quantity of Special Provision (Remove Commercial Sign) to be measured for payment will be the number of signs removed and returned to their owners in the complete and accepted work.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Remove and Reset Commercial Sign) will be paid for at the Contract unit price per each. Payment will be full compensation for removing the sign, sign post(s), and foundation(s); for transporting, handling, and temporarily storing the sign and

10/5/2011

post(s); for replacing rotted or unusable existing posts and providing new hardware and accessories as needed; for resetting the sign at the location indicated in the Plans or as directed by the Engineer; for performing any required excavation, foundation construction, and backfilling; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

The accepted quantity of Special Provision (Remove and Reset Commercial Sign with Wood Planter) will be paid for at the Contract unit price per each. Payment will be full compensation for removing the sign, sign post(s), planter, and foundation(s); for transporting, handling, and temporarily storing the sign, planter, and post(s); for replacing rotted or unusable existing posts and providing new hardware and accessories as needed; for resetting the sign and planter at the location indicated in the Plans or as directed by the Engineer; for performing any required rebuilding of planters, excavation, foundation construction, and backfilling; for re-using existing planting material or replacing with suitable planting material to the original grade in the planter; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

The accepted quantity of Special Provision (Remove Commercial Sign) will be paid for at the Contract unit price per each. Payment will be full compensation for removing the sign, sign post(s), and foundation(s); for transporting and handling the sign and post(s); for returning the sign and post(s) to the owner or as directed by the Engineer; for performing any required excavation, foundation construction, and backfilling; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

| <u>Pay Item</u>  | <u>Pay Unit</u> |
|--|-----------------|
| 900.620 Special Provision (Remove and Reset Commercial Sign)                   | Each            |
| 900.620 Special Provision (Remove and Reset Commercial Sign with Wood Planter) | Each            |
| 900.620 Special Provision (Remove Commercial Sign)                             | Each            |