

CUT HABITAT TREE

****From Cabot-Danville FEGC F 028-3(26) C/1**

- xx. DESCRIPTION. This work shall consist of providing cut trees with limbs intact at the locations indicated in the Plans to provide habitat for wildlife.
- xx. MATERIALS. Each tree shall be eight (8) to ten (10) inches in diameter at its base, and not less than fifteen (15) feet long. Each of the trees shall extend from the point shown in the Plans towards the center, with their tops towards the center. Cut habitat trees may be obtained from excavated areas of the mitigation site, from impact areas of the highway project, or from other locations available to the Contractor.
- xx. CONSTRUCTION REQUIREMENTS. Following completion of the plantings, two (2) cut habitat trees with limbs intact shall be placed into the south pond area as shown in the Plans. The trunk shall be located at the position shown in the Plans, with limbs facing towards the center of the pond.
- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Cut Habitat Tree) to be measured for payment will be for each tree planted in the complete and accepted work.
- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Cut Habitat Tree) will be paid for at the Contract unit price for each. Payment will be full compensation for furnishing, transporting, handling, and planting the tree, and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.620 Special Provision (Cut Habitat Tree)	Each