

10/5/2011

DECOMMISSION WELL

\*\*From Bennington AC NH 019-1(51)

\*\*From Hyde Park HES 030-2(23)

- xx. DESCRIPTION. This work shall consist of the abandonment of an existing water well at the location shown in the Plans and as directed by the Engineer.
- xx. MATERIALS. Mortar shall meet the requirements of Subsection 707.02.
- xx. TOOLS. Tools are to be new or clean and free from contaminants. Tools used to mix and pour mortar and that come in contact with groundwater shall be cleaned in a 10% bleach/water solution prior to use to ensure that any bacteria present does not get introduced to groundwater resources.
- xx. CONSTRUCTION REQUIREMENTS. Decommissioning of wells shall be performed in accordance with the Plans and as directed by the Engineer.
- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Decommission Water Well) to be measured for payment will be the number of wells decommissioned in the complete and accepted work.
- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Decommission Water Well) will be paid for at the Contract unit price for each. Payment will be full compensation for performing the required work, including but not limited to furnishing, transporting, handling, and placing the materials specified; removing casings, excavating, dewatering, placing temporary controls, excavation support, sheeting, and bracing; backfilling, disposing of water; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.620 Special Provision (Decommission Observation Well)	Each
900.620 Special Provision (Decommission Water Well)	Each