

DELINEATORS

****From Bloomfield-Lemington STP 2610(1)**

- xx. DESCRIPTION. This work shall consist of furnishing and installing delineators and reflector units on new posts at the locations indicated in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 676 of the Standard Specifications.

- xx. GENERAL REQUIREMENTS. Reflector units shall be of the shape and dimensions shown on the Plans and shall be installed on 45 mm (1.75 inch) square steel posts weighing 2.80 kg/m (1.88 lb/ft).

Final delineator configuration shall be as shown on the Plans.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Delineator with Steel Post) to be measured for payment will be the number installed in the complete and accepted work. No added measurement will be made for reflector units placed back-to-back on the same delineator post.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Delineator with Steel Post) will be paid for at the Contract unit price per each. Payment will be full compensation for furnishing, fabricating, transporting, handling, and installing the materials specified, including plaques where required, and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.620 Special Provision (Delineator with Steel Post)	Each