

GABION RETAINING WALL

****From Irasburg STP CULV(20)**

xx. DESCRIPTION. This work shall consist of furnishing and installing wire mesh gabion baskets and fill material in accordance with these specifications, in accordance with the lines, grades, and dimensions shown on the Plans, and as directed by the Engineer.

xx. MATERIALS. Materials shall meet the requirements of the following Subsections:

Rock Fill for Gabions.....706.06
Gabion Baskets.....712.04

xx. CONSTRUCTION REQUIREMENTS. The furnishing and installing of gabion baskets shall be performed in accordance with the manufacturer's recommendations.

The Contractor should expect to perform some manual stone placement to minimize voids and to create a neat, flat vertical surface of gabions.

xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Gabion Retaining Wall) to be measured for payment will be the number of cubic meters (cubic yards) of Rock Fill for Gabions placed in the complete and accepted work.

Excavation, geotextile fabric, and bedding material will be measured and paid for under the appropriate Contract items as indicated on the Plans.

xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Gabion Retaining Wall) will be paid for at the Contract unit price per cubic meter (cubic yard). Payment shall be full compensation for furnishing, transporting, handling, and placing the material specified and for furnishing all labor, materials, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.608 Special Provision (Gabion Retaining Wall)	Cubic Meter (Cubic Yard)