

INFILTRATION TRENCH

****From Waterbury CMG PARK(11)S (Re-advertised)**

xx. DESCRIPTION. This work shall consist of constructing an infiltration trench with specified material as detailed in the Plans and as directed by the Engineer.

xx. MATERIALS. Drainage aggregate shall meet the requirements of Subsection 704.16(a).

Geotextile shall meet the requirements of Section 720 for Geotextile for Underdrain Trench Lining.

xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Infiltration Trench) to be measured for payment will be the number of meters (linear feet) of infiltration trench installed in the complete and accepted work.

xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Infiltration Trench) will be paid for at the Contract unit price per meter (linear foot). Payment will be full compensation for performing the work specified and for furnishing all materials, including drainage aggregate and geotextile, labor, tools, equipment, and incidentals necessary to complete the work.

Excavation for Special Provision (Infiltration Trench) will be paid under Contract item 204.20.

Topsoil, seed, and mulch will be paid under their respective Contract items.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.640 Special Provision (Infiltration Trench)	Meter (Linear Foot)