

INSTALLATION OF STRUCTURAL STEEL

****From North Hero-Grand Isle BHF 028-1(21)**

These provisions are for use in installing pre-purchased materials. The Final Pay Quantity (FPQ) designation, if used, requires the inclusion of the associated Section 109 provisions.

xx. DESCRIPTION. This work shall consist of installing structural steel as detailed in the Plans.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 506 of the Standard Specifications, except that the provisions of Subsections 506.03, 506.04, 506.05, and 506.06 shall not apply.

xx. MATERIALS. The required materials for performing the work under this Section will be provided to the Contractor as indicated in the Plans.

xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Installation of Structural Steel) (FPQ) to be measured for payment will be the number of kilograms (pounds) of replacement and new structural steel used in the complete and accepted work.

xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Installation of Structural Steel) (FPQ) will be paid for at the Contract unit price per kilogram (pound). Payment will be full compensation for unloading the material at delivery, stockpiling, loading the material from stockpile, unloading, and installing the material in its final location as specified in the Contract Documents, and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.635 Special Provision (Installation of Structural Steel) (FPQ)	Kilogram (Pound)