

METAL HAND RAILING

****From Richford BHF 0302(3)S**

- xx. DESCRIPTION. This work shall consist of furnishing and erecting metal hand railing at the locations indicated in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 525 of the Standard Specifications.

- xx. MATERIALS. Materials for Metal Hand Railing shall meet the requirements specified in the Plans.

- xx. CONSTRUCTION REQUIREMENTS. Metal Hand Railing shall be installed as detailed on the Plans and as directed by the Engineer.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Metal Hand Railing) to be measured for payment will be the number of meters (linear feet) of railing placed in the complete and accepted work, measured within the pay limits designated in the Plans.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Metal Hand Railing) will be paid for at the Contract unit price per meter (linear foot). Payment will be full compensation for detailing, furnishing, handling, and placing the materials specified; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment for applying protective coatings will be made under the appropriate Section 513 items in the Contract.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.640 Special Provision (Metal Hand Railing)	Meter (Linear Foot)