

NESTING BOX AND POST

****From Cabot-Danville FEGC F 028-3(26) C/1**

- xx. DESCRIPTION. This work shall consist of constructing nesting boxes with posts at the locations indicated in the Plans and as directed by the Engineer to provide nesting opportunities for bluebirds.
- xx. MATERIALS. Materials shall meet the requirements specified in the Plans.
- xx. CONSTRUCTION REQUIREMENTS. Nesting boxes with posts shall be constructed and placed as shown in the Plans.
 - (a) Bluebird Boxes. Entrance holes of boxes shall face north to east. The boxes shall be placed in open grassy areas that are accompanied by widely scattered trees and shrubs. As directed and/or approved by the Engineer, locations of boxes may vary slightly from Plan locations to accommodate the above concerns.
 - (b) Wood Duck Boxes. Boxes shall be placed so as to not be visible to each other, with entrance holes not facing each other. Locations indicated in the Plans may be varied enough to achieve separation requirements as approved by the Engineer.
- xx. METHOD OF MEASUREMENT. The quantities of Special Provision (Bluebird Box and Post) and Special Provision (Wood Duck Box and Post) to be measured for payment will be for each box with post installed in the complete and accepted work.
- xx. BASIS OF PAYMENT. The accepted quantities of Special Provision (Bluebird Box and Post) and Special Provision (Wood Duck Box and Post) will be paid for at the Contract unit price for each. Payment will be full compensation for furnishing, transporting, handling, and installing the materials specified, and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.620 Special Provision (Bluebird Box and Post)	Each
900.620 Special Provision (Wood Duck Box and Post)	Each