

10/5/2011

PARTIAL REMOVAL AND MODIFICATION OF VERMONT JOINT

**\*\*From Bennington-Shaftsbury BHF MEMB(3)**

xx. DESCRIPTION. This work shall consist of partially removing and modifying an existing Vermont Joint(s) at the location(s) indicated in the Plans and as directed by the Engineer.

xx. CONSTRUCTION REQUIREMENTS. The Contractor shall remove and dispose of existing Vermont Joint expansion plates, drain trough(s), and associated hardware.

The Contractor shall grind existing shoulder concrete to the configuration shown on the Plans. The final surface shall be to the satisfaction of the Engineer.

xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Partial Removal and Modification of Vermont Joint) to be measured for payment will be the number of meters (linear feet) of bridge joint removed and modified in the complete and accepted work, measured along its centerline.

xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Partial Removal and Modification of Vermont Joint) will be paid for at the Contract unit price per meter (linear foot). Payment will be full compensation for partially removing and modifying the existing Vermont Joint(s) as specified and as detailed in the Plans, and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.640 Special Provision (Partial Removal and Modification of Vermont Joint)	Meter (Linear Foot)