

PEDESTRIAN SIGNAL HEADS

**\*\*From Burlington-South Burlington NH 2624(1)**

- xx. DESCRIPTION. This work shall consist of removing existing pedestrian signal heads and furnishing and installing new pedestrian signal heads with ADA push buttons and audible signals at the locations indicated in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 678 of the Standard Specifications.

- xx. MATERIALS. Materials for pedestrian signal heads shall meet the requirements specified in the Plans.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Pedestrian Signal Heads, Countdown) to be measured for payment will be the number of each intersection with signal heads removed and installed in the complete and accepted work.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Pedestrian Signal Heads, Countdown) will be paid for at the Contract unit price per each at each designated intersection. Payment will be full compensation for removing existing signal heads; furnishing, transporting, handling, and installing the materials specified; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.620 Special Provision (Pedestrian Signal Heads, Countdown)(US Alt. Route 7 @ Pearl St.)	Each