

PIPE SLOPE DRAIN

****From Bennington AC NH 019-1(54)**

xx. DESCRIPTION. This work shall consist of furnishing, installing, maintaining, and removing pipe slope drains at the locations shown in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Sections 601 and 653 of the Standard Specifications.

xx. MATERIALS. Materials shall meet the requirements of the following Subsections:

Stone		for
Riprap.....	706.03	
Corrugated		Steel
Pipe.....	711.01	

xx. CONSTRUCTION REQUIREMENTS. Pipe Slope Drain shall be installed in accordance with the Plans and as directed by the Engineer.

xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Pipe Slope Drain) to be measured for payment will be on a per unit basis in the complete and accepted work.

xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Pipe Slope Drain) will be paid for at the Contract unit price for each. Payment will be full compensation for furnishing, transporting, handling, placing, and removing the material specified and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work. Geotextile, stone fill, or any other items necessary to complete the work shall be considered incidental to Special Provision (Pipe Slope Drain).

Unless otherwise specified in the Contract, payment for the maintenance of Pipe Slope Drain will be incidental to Special Provision (Pipe Slope Drain).

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.620 Special Provision (Pipe Slope Drain)	Each