

PROTECTIVE SCREENING

****From Bennington AC NH 019-1(53)**

- xx. DESCRIPTION. This work shall consist of furnishing and erecting protective screening at the locations indicated in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 620 of the Standard Specifications.

- xx. MATERIALS. Materials shall meet the following requirements:
 - (a) Wire Fabric. Wire fabric shall be a 50 mm (2 inch) mesh, galvanized, steel chain-link fabric conforming to the requirements of Subsection 727.02.
 - (b) Hardware. Hardware shall be hot-dip galvanized or mechanically galvanized using a mechanically deposited process conforming to the requirements of AASHTO M 298, Class 110.

- xx. CONSTRUCTION REQUIREMENTS. Protective Screening shall be installed as shown on the Plans or as directed by the Engineer.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Protective Screening) to be measured for payment will be the number of meters (linear foot) installed in the complete and accepted work. Measurement will be along the top of the screening from outside to outside of end posts for each continuous run of fence.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Protective Screening) will be paid for at the Contract unit price per meter (linear foot). Payment will be full compensation for furnishing, transporting, handling, and placing the materials specified, including but not limited to the screening, posts, rails, and connections, and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.640 Special Provision (Protective Screening)	Meter (Linear Foot)