

REMOVE EXISTING OVERHEAD SIGN ASSEMBLY

\*\*From Barre City FEGC F 026-1(34) C/1

\*\*From Barre City FEGC F 026-1(34) C/2

- xx. DESCRIPTION. This work shall consist of removing and disposing of an existing overhead sign assembly(ies) at the location(s) indicated in the Plans and as directed by the Engineer.
- xx. CONSTRUCTION REQUIREMENTS. The Contractor shall remove the entire sign assembly, including concrete footings, to a depth of 450 mm (18 inches) below grade. Areas of ground disturbance shall be restored to the satisfaction of the Engineer.
- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Remove Existing Overhead Sign Assembly) of the type specified to be measured for payment will be the number of each assembly removed in the complete and accepted work.
- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Remove Existing Overhead Sign Assembly) of the type specified will be paid for at the Contract unit price per each. Payment will be full compensation for removing and disposing of assembly components, including concrete footings; for performing any excavation necessary; for restoring areas of ground disturbance; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Costs associated with providing traffic control and/or flaggers for performing the work will be paid under the appropriate Contract item(s).

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.620 Special Provision (Remove Existing Overhead Sign Assembly, Cantilever)	Each
900.620 Special Provision (Remove Existing Overhead Sign Assembly, Multi-Support)	Each