

REMOVING, REFURBISHING, AND RESETTING LIGHT POST

****From Springfield BHF 016-2(14)**

- xx. DESCRIPTION. This work shall consist of removing, refurbishing, and resetting existing light post(s) at the locations shown in the Plans and as directed by the Engineer.
- xx. CONSTRUCTION REQUIREMENTS. The Contractor shall remove, clean, repair, paint, and reset the existing light post. The refurbished light post shall be reset on a new concrete railing post as detailed in the Plans.

Cleaning and painting shall be performed in accordance with Section 513. The final coat of paint shall be black in conformance with Subsection 708.03.

Wiring and fusing within poles and bases shall be performed in accordance with Section 678.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Removing, Refurbishing, and Resetting Light Post) to be measured for payment will be the number of light posts refurbished and reset in the complete and accepted work.
- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Removing, Refurbishing, and Resetting Light Post) will be paid for at the Contract unit price per each. Payment will be full compensation for removing, cleaning, repairing, painting, including containment and environmental protection measures, and resetting the light post; transporting the light post to and from a fabrication shop; furnishing anchoring hardware; performing all work associated with restoring the lighting to working order, including anchoring the light post and luminaire, providing power, wiring, and fusing, testing, and furnishing lamps; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Wired conduit and concrete and reinforcing steel for posts will be paid for separately under the appropriate Contract items.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.620 Special Provision (Removing, Refurbishing, and Resetting Light Post)	Each