

SPLIT RAIL FENCE

****From Randolph CMG PARK(21)S)**

- xx. DESCRIPTION. This work shall consist of furnishing and erecting split rail fence at the locations shown in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 620 of the Standard Specifications.

- xx. MATERIALS. Fence rails and posts shall be made of Premium Native White Cedar. This material shall be resistant to insects and rot and shall be free of any chemicals or toxic preservatives and/or treatments.

Material of equal quality, detail, function, and performance to that provided by the following supplier, or approved equal, shall be used:

F. E. Hart Fence Company, Inc.
394 Shunpike Road
Williston, VT 05495
Tel: (802)339-3219

- xx. ERECTION OF SPLIT RAIL FENCE. Fencing shall be erected at the locations shown in the Plans and as directed by the Engineer.

Posts and rails shall be installed true, plumb, and level at the spacing and depths shown in the Plans. Rails shall be secure in place by the "Farmlock" system.

The use of explosive fasteners, screws, or nailing for securing framing and blocking will not be allowed unless approved by the Engineer.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Split Rail Fence) to be measured for payment will be the number of meters (linear feet) of split rail fence erected in the complete and accepted work. Measurement will be along the face of rail from outside to outside of end posts for each continuous run of fence.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Split Rail Fence) will be paid for at the Contract unit price per meter (linear foot). Payment will be full compensation for furnishing, transporting, handling, assembling, and placing the materials specified, and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.640 Special Provision (Split Rail Fence)	Meter (Linear Foot)