

STEEL BEAM GUARDRAIL REPAIR

****From Hartland-Norwich IM 091-1(59)**

- xx. DESCRIPTION. This work shall consist of furnishing and installing new steel beam guardrail components as shown in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions and Section 621 of the Standard Specifications.

- xx. MATERIALS. Materials for replacement components shall meet the following requirements:

- (a) Delineator. Delineators designated for replacement shall be replaced with materials meeting the requirements of Agency Standard Drawing G-1.

- (b) Offset Block. Offset blocks designated for replacement shall be replaced in-kind. Materials shall be in conformance with the applicable requirements of Subsection 728.01 for either wood, steel, or alternative blockouts.

- xx. GENERAL REQUIREMENTS. Prior to beginning the work, the Contractor shall verify with the Engineer the guardrail components to be replaced. Those components that are designated for replacement shall be marked in such a manner that they can be later identified for replacement.

The work shall be performed in accordance with applicable Agency Standard Drawings.

- xx. METHOD OF MEASUREMENT. The quantities of Special Provision (Steel Beam Guardrail Delineator) and Special Provision (Steel Beam Guardrail Offset Block) to be measured for payment will be the number of each component replaced in the complete and accepted work.

- xx. BASIS OF PAYMENT. The accepted quantities of Special Provision (Steel Beam Guardrail Delineator) and Special Provision (Steel Beam Guardrail Offset Block) will be paid for at the Contract unit price for each. Payment will be full compensation for removing and disposing of the damaged guardrail component; for furnishing, transporting, handling, and installing the replacement component; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.620 Special Provision (Steel Beam Guardrail Delineator)	Each
900.620 Special Provision (Steel Beam Guardrail Offset Block)	Each