

TEMPORARY RESERVOIR OUTLET PROTECTION

****From Bennington AC NH 019-1(52)**

xx. DESCRIPTION. This work shall consist of furnishing, installing, maintaining, and removing temporary reservoir outlet protection devices at the locations shown in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 653 of the Standard Specifications.

xx. MATERIALS. Materials shall meet the requirements of the following Subsections:

Stone for Stone Fill, Type II.....706.04(b)

Geotextile fabric shall conform to the requirements of Section 720 for Geotextile Under Stone Fill.

xx. CONSTRUCTION REQUIREMENTS. Temporary reservoir outlet protection devices shall be installed in accordance with the Plans.

xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Temporary Reservoir Outlet Protection) to be measured for payment will be the number of cubic meters (cubic yards) of the stone specified used in the complete and accepted work.

xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Temporary Reservoir Outlet Protection) will be paid for at the Contract unit price per cubic meter (cubic yard). Payment will be full compensation for furnishing, transporting, handling, placing, and removing the material specified and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work. Geotextile, stone fill, or any other items necessary to complete the work shall be considered incidental to Special Provision (Temporary Reservoir Outlet Protection).

Unless otherwise specified in the Contract, payment for the maintenance of Temporary Reservoir Outlet Protection will be incidental to Special Provision (Temporary Reservoir Outlet Protection).

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.608 Special Provision (Temporary Reservoir Outlet Protection)	Cubic Meter (Cubic Yard)