

TEMPORARY SEDIMENT BASIN

**\*\*From Danville FEGC 028-3(32)**

- xx. DESCRIPTION. This work shall consist of constructing a temporary outlet control device, performing periodic sediment removal, and removing the temporary outlet control device at the location(s) indicated in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 653 of the Standard Specifications.

- xx. MATERIALS. Materials shall meet the requirements shown in the Plans.

- xx. METHOD OF MEASUREMENT. The accepted quantity of Special Provision (Temporary Sediment Basin) to be measured for payment will be the number of each temporary sediment basin installed in the complete and accepted work.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Temporary Sediment Basin) will be paid for at the Contract unit price for each. Payment shall be full compensation for furnishing, transporting, handling, and installing the necessary materials, including constructing a temporary outlet control device, performing periodic sediment removal, and removing the temporary outlet control device, and for furnishing all labor, materials, equipment, tools, and incidentals necessary to complete the work.

Earthwork, stone outlet protection, pipes, vegetated treatment swales, EPSC devices, spillways, cut-off trench, dewatering devices, anti-seep collar, and all other items required to build the permanent operational stormwater detention pond will be paid separately under the appropriate Contract items.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.620 Special Provision (Temporary Sediment Basin)	Each