

TEMPORARY THRESHOLD LIGHTS

****From Highgate AIR 04-3183**

- xx. DESCRIPTION. This work shall consist of furnishing, installing, and removing temporary threshold lights at the locations indicated in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Federal Aviation Administration (FAA) specification *L-125 Installation of Airport Lighting Systems*.

- xx. MATERIALS. Materials shall meet the requirements of FAA specification *L-125 Installation of Airport Lighting Systems*, with the following exception:

Concrete shall meet the requirements of Section 541 for Concrete, Class B.

- xx. METHOD OF MEASUREMENT. The quantity of Special Provision (Temporary Threshold Lights) to be measured for payment will be the number of each threshold light unit placed and removed in the complete and accepted work.

- xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (Temporary Threshold Lights) will be paid for at the Contract unit price for each. Payment will be full compensation for furnishing, preparing, assembling, installing, and removing the materials specified, including but not limited to transformers, light bases, weed barrier, and temporary stakes; and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.620 Special Provision (Temporary Threshold Lights)	Each