

UTILITY EQUIPMENT

****From Danville FEGC 028-3(32)**

- xx. DESCRIPTION. This work shall consist of installing utility furnished buried cable pedestals, meter pedestals, transformers, and vaults for utilities, removing existing meter sockets, furnishing and installing new meter sockets, and making service connections at the meter and electrical panel at the locations indicated in the Plans and as directed by the Engineer.
- xx. MATERIALS. Materials shall conform to the requirements of the respective utility company specifications.
- xx. CONSTRUCTION REQUIREMENTS. Buried cable pedestals, meter pedestals, meter sockets, transformers, and vaults shall be installed in accordance with the Plans and the respective utility company specifications. The Contractor shall obtain specifications directly from the utility companies.

See Special Provision No. **xx** for utility company contact information.

The Contractor shall install the buried cable pedestals, meter sockets, transformers, and vaults, including all wired conduit associated with these items. The utility company will install meters and make service connections in the transformer/pedestal as required for putting the transformers and vaults in service.

- xx. METHOD OF MEASUREMENT. The quantities of Special Provision (Buried Cable Pedestal), Special Provision (CVPS 1 Phase Transformer), Special Provision (CVPS 3 Phase Vault), Special Provision (J Vault) of the size specified, Special Provision (Meter Pedestal), and Special Provision (Replacement of Existing Meter Socket) to be measured for payment will be the number of each installed or replaced in the complete and accepted work.
- xx. BASIS OF PAYMENT. The accepted quantities of Special Provision (Buried Cable Pedestal), Special Provision (CVPS 1 Phase Transformer), Special Provision (CVPS 3 Phase Vault), Special Provision (J Vault) of the size specified, Special Provision (Meter Pedestal), and Special Provision (Replacement of Existing Meter Socket) will be paid for at the Contract unit price for each. Payment will be full compensation for performing the work specified, and for furnishing all materials, labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.620 Special Provision (Buried Cable Pedestal)	Each
900.620 Special Provision (CVPS 1 Phase Transformer)	Each
900.620 Special Provision (CVPS 3 Phase Vault)	Each
900.620 Special Provision (J Vault)	Each
(x M (x") X x M (x") X x M (x"))	
900.620 Special Provision (Meter Pedestal)	Each
900.620 Special Provision (Replacement of Existing Meter Socket)	Each