

VAST SIGN CEDAR POST

****From Cabot-Danville FEGC F 028-3(26) C/1**

xx. DESCRIPTION. This work shall consist of furnishing and placing cedar posts for signs for defining Vermont Association of Snow Travelers (VAST) trail(s) at the locations indicated in the Plans and as directed by the Engineer.

The work under this Section shall be performed in accordance with these provisions, the Plans, and Section 619 of the Standard Specifications.

xx. MATERIALS. Posts shall be cedar and shall be four (4) inches X four (4) inches X eight (8) feet long.

xx. CONSTRUCTION REQUIREMENTS. Posts shall be set in pairs at the locations indicated in the Plans. Posts shall be set four (4) feet below the ground surface. Posts in pairs shall be separated from each other by 20 linear feet.

Signs will be supplied and affixed to posts by others.

xx. METHOD OF MEASUREMENT. The quantity of Special Provision (VAST Sign Cedar Post) to be measured for payment will be for each post installed in the complete and accepted work.

xx. BASIS OF PAYMENT. The accepted quantity of Special Provision (VAST Sign Cedar Post) will be paid for at the Contract unit price for each. Payment will be full compensation for furnishing, transporting, handling, and installing the post, and for furnishing all labor, tools, equipment, and incidentals necessary to complete the work.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
900.620 Special Provision (VAST Sign Cedar Post)	Each